

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Ben Griffin of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: C.B. and J. B. Oil Company

Complete Address: R. R. #1, Natoma, Kansas 67650

Lease Name: Chrisler "B" Well No. #1

Location: NW SW NW Sec. 25 Twp. 11 Rge. 16 (E) (W)

County: Ellis Total Depth: 3441'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Griffin was instructed to plug the well as follows:

8 5/8"-907' s.p. cuc. w/350 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

- 1st plug @ 720' w/70 sacks cement
- 2nd plug @ 310' w/40 sacks cement
- 3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement
- Circulate 10 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

FFR - 2 1982

[Signature]
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas