

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-159-02472-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date COMPLETION, 8/52

Well Operator: T-N-T Engineering, Inc. KCC License #: 33699
(Owner / Company Name) (Operator's)

Address: 3711 MAPLEWOOD, SUITE 201 City: WICHITA FALLS

State: TEXAS Zip Code: 76308 Contact Phone: (620) 786-5514

Lease: H ROTH Well #: 5 Sec. 29 Twp. 19 S. R. 10 East West

NE - NE - NE Spot Location / QQQQ County: RICE

3304972 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

380462 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 452' Cemented with: 275 Sacks

Production Casing Size: 5-1/2" Set at: 3282' Cemented with: 155 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3060-86', 3158-68', 3275-78', 3282'-3325' PBDT @ 3283' w/ hydromite
1250 2 900 35 500 cor

Elevation: 1771/1775 (G.L. / K.B.) T.D.: 3325' PBDT: 3283 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS PER KCC REGULATIONS
Sand 2990 + 55XS 1640 R.C.C.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 09 2009

CONSERVATION DIVISION
WICHITA, KS

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: RICKEY POPP, AGENT FOR T-N-T ENGINEERING

Phone: (620) 786-5514

Address: PO BOX 187 City / State: HOISINGTON, KS 67544

Plugging Contractor: QUALITY WELL SVC KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 W MAIN LYONS, KS 67554 Phone: (620) 727-3410

Proposed Date and Hour of Plugging (if known?): NO DATE SET BUT TOWARDS END OF APRIL / FIRST OF MAY 6-1-07 11:30 Am

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/26/07 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* Well plugged - KCC PKT

Dist 2
PKT

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
6/4/2007	872

Bill To
TNT Engineering, Inc. 3711 Maplewood, Ste. 201 Wichita Falls, TX 76308

P.O. No.	Terms	Lease Name
		H Roth 5

Description	Qty	Rate	Amount
Rig Time	22.5	175.00	3,937.50T
Floor Rental		125.00	125.00T
Sand		35.00	35.00T
Cement	5	9.00	45.00T
Shots	2	160.00	320.00T
Torch		50.00	50.00T
Water Truck	6.5	75.00	487.50T
Backhoe	5	75.00	375.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
Fresh Water		20.00	20.00T
<p>5-29-07 Drove to location, backed rig in, drove home.</p> <p>5-31-07 Drove to location. raised pole. checked hole, sanded off bottom. loaded hole with water. dug cellar. cut nipple out of 5 1/2". cut bolts off 4 bolt head. set floor, pulled slips. checked hole, sand was at 2990'. bailed 5 sacks cement with bailer, had 14" stretch, ripped casing at 1860', worked pipe, ripped casing at 1640', pipe came free. pulled casing up to 1250'. swedge in, drove home.</p> <p>6-1-07 Drove to location, had to wait on cement, pumped 35 sacks, 150# hulls at 1250', pulled to 900', pumped 35 sacks 150# hulls, pulled to 500', circulated with 130 sacks 100# hull. pulled rest of casing, tore down floor and rig, emptied pit. cleaned up location.</p>			

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 09 2009
CONSERVATION DIVISION
WICHITA, KS

Subtotal	\$5,450.00
Sales Tax (6.3%)	\$343.35
Total	\$5,793.35