

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - -047-20,161 - 00 - 00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 01/1975

Well Operator: F.G. HOLL COMPANY L.L.C. KCC License #: 5056
(Owner / Company Name) (Operator's)

Address: 9431 E. Central Suite #100 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481

Lease: Newsom Well #: 1-21 Sec. 21 Twp. 24 S. R. 17 East West

- C - NW - SE Spot Location / QQQQ County: Edwards

1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: NONE Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 256'KB Cemented with: 235 Sacks

Production Casing Size: 4 1/2" Set at: 4470' KB Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Mississippi @ 4356'-4369'

Elevation: 2121 (G.L. / K.B.) T.D.: 4770' PBTD: 3580' Anhydrite Depth: 1136'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): HEAVY MUD, HULLS, CEMENT AND PLUG ACCORDING TO KCC.

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

FEB 09 2009

If not explain why? _____
CONSERVATION DIVISION
WICHITA KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: ROB LONG

Phone: (620) 793 - 0915


Address: P.O. BOX 158 City / State: BELPRE/KANSAS

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925
(Company Name) (Contractor's)

Address: 190 US HIGHWAY 56 ELLINWOOD/KANSAS Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 02/02/2009 Authorized Operator / Agent: Adam T. Thorne 
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist.
PKT

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- NEWSOM #1
Located: C NW SE, Section 21-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 4, 1975
COMPLETED: January 15, 1975

TOTAL DEPTH: 4471'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 200 Clay, Sand, Shale	Ran 6 joints used 8 5/8" 20# 8RD casing, 244' set at 256' I.B. with 235 sacks 60/40 Pozmix, 3% cc. Plug down at 3:00 AM, 1-5-75.
200 - 259 Shale	
259 - 1025 Shale, Sand, Red Bed	
1025 - 1136 Shale and Shells	
1136 - 1153 Anhydrite	
1153 - 2135 Shale and Shells	
2135 - 3160 Lime and Shale	
3160 - 3600 Lime	
3600 - 3770 Lime and Shale	
3770 - 3869 Shale	
3869 - 4383 Lime	
4383 - 3305 Shale and Sand	
4405 - 4410 Kinderhook	
4410 - 4440 Lime and Shale	
4440 - 4471 Kinderhook and Viola	Ran 135 joints new 10.5# casing, 4480' set at 4470' K.B. with 100 sacks 50/50 Pozmix with 2% gel and 18% salt and .75% CFR2 and 1/4# Flocele per sack and 5# gilsonite per sack and 1/8# Tuffiber per sack. Plug down at 1:00 AM, 1-15-75.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 09 2009

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

February 10, 2009

Re: NEWSOM #1-21
API 15-047-20161-00-00
21-24S-17W, 1980 FSL 1980 FEL
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after August 9, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888