

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 151-22,038 - 00 - 00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 2/27/1991 spud

Well Operator: F.G. HOLL COMPANY L.L.C. KCC License #: 5056  
(Owner / Company Name) (Operator's)

Address: 9431 E. Central Suite #100 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481  
*Schraver* *KCC OKT P&A* *RBDMS*

Lease: Schraver "A" Well #: 1-32 Sec. 32 Twp. 29 S. R. 13  East  West

150' S - E/2 - SW - SW Spot Location / QQQQ County: PRATT

510 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

4290 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 13 3/8" Set at: 286' Cemented with: 275 Sacks

Surface Casing Size: 13 3/8" Set at: 286' Cemented with: 275 Sacks

Production Casing Size: 4 1/2" Set at: 4812' Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4,534'-4,550'

Elevation: 1962' ( G.L. /  K.B.) T.D.: 4813' PBTD: none Anhydrite Depth: 805'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): HEAVY MUD, HULLS, CEMENT AND PLUG ACCORDING TO KCC.

RECEIVED  
KANSAS CORPORATION COMMISSION  
**FEB 09 2009**  
CONSERVATION DIVISION  
WICHITA, KS

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: ROB LONG

Phone: (620) 793 - 0915

Address: P.O. BOX 158 City / State: BELPRE/KANSAS

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925  
(Company Name) (Contractor's)

Address: 190 US HIGHWAY 56 ELLINWOOD/KANSAS Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 2/02/2009 Authorized Operator / Agent: Adam T. Thorne *Adam T. Thorne*  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*KCC OKT P&A*  
*Open Leases*  
*no conductor casing*

*Dust*  
*PLG*

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

SAMPLE LOG -----SHRIVER A #1-32  
150' S of E/2 SW SW, Sec. 32-T29S-R13W, Pratt County, Ks.

OWNER: F. G. Holl Family Trust

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

STARTED: February 27, 1991

COMPLETED: March 9, 1991

TOTAL DEPTH 4800' RFD  
4808' LTD

## LOG

0 - 150' Surface soil & sand  
150 - 289' Red bed  
289 - 750' Shale & Red bed  
750 - 1778' Shale  
1778 - 4813' Lime & shale

## CASING RECORD

Ran 6 joints 13 3/8" 48# new casing. 274.27'  
pipe set at 286' KB. Cemented with 275 sacks  
60/40 Pozmix W/ 2% gel & 3% cc. Plug down at  
2:30PM 2-27-91 by Howco. Good returns to  
surface.

Ran 133 joints 4 1/2" 10.5# used casing. 4804.94'  
pipe set at 4812' KB. Cemented with 100 sacks  
Lite followed with 150 sacks F. G. Holl mix  
W/ 20 bbl salt flush and 500 gallons super  
flush ahead of cement. Plug down at 5:00 AM  
3-9-91 by Howco

## DEVIATION SURVEYS

4493' - 2°  
4813' - 2 1/4°

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 09 2009

CONSERVATION DIVISION  
WICHITA KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

HOLL, F.G., COMPANY L.L.C.  
9431 E CENTRAL STE 100  
WICHITA, KS 67206-2563

February 10, 2009

Re: SCHRIVER A #1-32  
API 15-151-22038-00-00  
32-29S-13W, 510 FSL 4290 FEL  
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after August 9, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888