

15-065-02838-0001
9-27

6 031436

API NUMBER 15- _____ 1955

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE, SEC. 5, T 9 S, R 24 W/Ex

TECHNICIAN'S PLUGGING REPORT

4950 feet from S section line

330 feet from E section line

Operator License # 30420

Lease Name Holley Unit²⁷ Well # 15-1

Operator: V. J. I. Natural Resources

County Graham 130.81

Name & Address 1503 Vine Street

Well Total Depth 4025 feet

Hays, Kansas 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well _____ Gas Well _____ Input Well xx SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Hays, Kansas

Company to plug at: Hour: PM _____ Day: 27 Month: Sept Year: 19 90

Plugging proposal received from Jason Dinges

(company name) V. J. I. (phone) _____

were: 8 5/8 set at 240 w/200 sks. cwc 5 1/2 set at 4025 PBD 3987.

Perfs 3954 - 78. Order 350 sks 65/35 poz 8% gel 500 lbs. hulls.

B.J. Titan Newman Water Truck. Shots at 2150 anhy - 1300 Kiowa. Hole open to prod. Perfs.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: ~~Atxxx~~ Part _____ None _____

Operations Completed: Hour: 1:15PM Day: 27 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT

Sq annulus w/100 sks cement blend w/100 lbs. hulls mixed into max psi 400 lbs. Close in psi 200 lbs. Sq 5 1/2 w/250 sks cement blend w/400 lbs. hulls mixed into last 100 sks to max psi 800 lbs. Close in psi 200 lbs. plug complete.

Remarks: (If additional description is necessary, COME BACK of this form.)

INVOICED

DATE 10-18-90

INV. NO. 29637

RECEIVED

10-17-90
OCT 17 1990
Signed

Carl Goodrow (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

Carl Goodrow FORM CP-2/3 Rev. 01-84

9-27 JAN 10 1991