

API NUMBER 15- - 065-21.212-0006

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE-NW-SE, SEC. 9, T 9 S, R 24 W/E

\_\_\_\_\_ FEET FROM N/S SECTION LINE  
\_\_\_\_\_ FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5560

LEASE NAME HEITH WELL # 1

OPERATOR: DAVIS BROS. OIL PRODUCERS INC.  
NAME & ADDRESS  
ONE WILLIAMS CENTER  
#260  
TULSA, OKLAHOMA,  
74172

COUNTY GRAHAM  
WELL TOTAL DEPTH 4085 \$132.76 FEET  
CONDUCTOR PIPE: SIZE 0 FEET  
SURFACE CASING: SIZE 8 5/8 FEET 217

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR HALLIBURTON OIL WELL CEM. LICENSE NUMBER 5287

ADDRESS EAST 8<sup>TH</sup> ST. HWY. 40 HAYS, KANS. 67601

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 25<sup>TH</sup> MONTH: JULY YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM CHARLES G. ARNOLD

(COMPANY NAME) DAVIS BROS. OIL PRODUCING INC. (PHONE) 913-434-7116

WERE: 8 5/8" 217<sup>FT</sup> SQ. CUL<sup>TM</sup> / 160<sup>ENT.</sup> - 4 1/2" OSG. SET @ 4083<sup>FT</sup> / 200<sup>ENT.</sup>

PLUG BACK T.D. 3855<sup>FT</sup>, PERFS. 3832' AND 4052', NO PIPE RECOVERY.

D.V. TOOL SET @ 2170<sup>FT</sup> EI<sup>TM</sup> / 500<sup>ENT.</sup> CUC.

ORDER 140<sup>ST</sup> 50% Pozmix 6% GEL-3% CA-CL, 12<sup>ST</sup> GEL, 3<sup>ST</sup> HULL'S, & 4 1/2" PLUG

PUMP IN WITH PUMP TRUCK. IN ANNULUS. AND IN 4 1/2" OSG.

PLUGGING PROPOSAL RECEIVED BY Martin Schmidt  
(TECHNICIAN) DOIC

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 2:45 PM DAY: 25<sup>TH</sup> MONTH: JULY YEAR: 1983

ACTUAL PLUGGING REPORT \_\_\_\_\_

ORDERED 140<sup>ST</sup> 50% Pozmix 6% GEL-3% CA-CL, 12<sup>ST</sup> GEL, 3<sup>ST</sup> HULL'S  
AND 4 1/2" PLUG.

PUMPED IN ANNULUS. 10<sup>ST</sup> ENT. MAX. PRESSURE 700<sup>PSI</sup>

PUMPED IN 4 1/2" OSG., 10<sup>ST</sup> ENT., 25<sup>ST</sup> ENT. 1/2<sup>ST</sup> HULL'S MIXED IN,  
12<sup>ST</sup> GEL. 1/2<sup>ST</sup> HULL'S, RELEASED PLUG AND 95<sup>ST</sup> ENT., MAX PRESSURE 580<sup>PSI</sup>

REMARKS: CEMENTED BY HALLIBURTON CEM.

RECEIVED  
STATE CORPORATION COMMISSION  
8-01-83  
AUG 01 1983

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

SIGNED Martin Schmidt  
(TECHNICIAN) DOIC

INVOICED

DATE 8-2-83  
INV. NO. 5043-W

FORM CP-213  
REV. 6-83