

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01611-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 9-9S-24W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: HILDEBRAND Well Number: 2  
County: GRAHAM Total Vertical Depth: 4065 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 SOUTH MAIN STE 200  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4064  
Surface Casing Size: 8.625 feet: 190

*132''*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/23/2003 12:00 PM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 735-9412

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Perfs 3942' - 3949'.  
Sand in casing 50' above perfs at 3880'. Packer at 3930'.  
Squeeze holes at 1884' and 2836'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/23/2003 3:00 PM

KCC Agent: PAT STAAB

**Actual Plugging Report:**

Perf Tech RIH and perforated at 2180' and 1025'. Ran wire line to TD - 3781'.  
Express Well Service RIH with tubing to 3420'.  
Swift Services pumped 30 sxs 60/40 pozmix neat followed with 70 sxs mixed with 300# hulls.  
Express pulled tubing to 2300'.  
Swift pumped 155 sxs cement mixed with 100# hulls - cement circulated to surface.  
Pulled tubing - tied onto 5 1/2" casing - pumped 35 sxs cement.  
Max. P.S.I. 750#. S.I.P. 500#.  
Tied onto backside - pumped 10 sxs 60/40 pozmix - cement circulated up around well head.

RECEIVED  
7-28-03  
JUL 28 2003  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #5765.

Plugged through: TBG

District: 04

Signed

*Pat Staab*

(TECHNICIAN)

INVOICED

7-28-03

170

2004060234

Form CP-2/3

JUL 24 2003

DAVIS BROS #2 HILDEBRAND 9-9-24W  
 NE NW NW

Contr. TRANSIT CORP GRAHAM County

E 2447<sup>38</sup> Comm. Comp. 11-28-58 IP 50 BOPD

Tops	Depth	Datum	Casing
ANH	2150	297	8" 190
			5" 4064
HEEB	3747	-1300	DST 3926-92/90", 65' SL OCM, BHP 110# PERF 3942-49: ACID 5000: SWB 5 BOPH 157'-164'
TOR	3768	-1321	
LANS	3785	-1338	
B/KC	4014	-1567	
			HOLLEY POOL
TD	4065	-1618	

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS
