

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00769-00-00  
Spot: NENENW , Sec/Twnshp/Rge: 9-9S-24W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: HILDEBRAND Well Number: 1  
County: GRAHAM Total Vertical Depth: 3995 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 SOUTH MAIN STE 200  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3990 125 SX CMT  
Surface Casing Size: 8.625 feet: 180 150 SX CMT *\$12984*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/23/2003 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 735-9412

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Perfs 3909' - 3914'; 3915' - 3916'.  
Tubing stuck at 3350' - pump stuck in hole.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/23/2003 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 2150' and 975' with a two shot perf. Shot-off tubing at 2980'.  
Express Well Service RIH with tubing to 2950' - pumped 40 sxs 60/40 pozmix neat followed with 60 sxs mixed with 300# hulls.  
Pulled tubing to 2200' - pumped 135 sxs 60/40 pozmix with 100# hulls - cement circulated to surface.  
Pulled tubing - tied onto 5 1/2" casing - pumped 40 sxs cement.  
Max. P.S.I. 600#. S.I.P. 400#.  
Tied onto backside - pumped 50 sxs 60/40 pozmix.  
Max. P.S.I. 150#. S.I.P. 100#.

RECEIVED  
7-28-03  
JUL 28 2003  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #5764.

Plugged through: TBG

District: 04

Signed *Patricia A. ...*  
(TECHNICIAN)

INVOICED

DATE 7-28-03

INVOICE NO. 2004060234

Form CP-2/3

JUL 24 2003

DAVIS BROS

#  
IT

HIDEBRAND

9-9-24W  
NE NE NW

Contr. TRANSIT DRILLING

GRAHAM

County

E 2417 Comm. 9-15-55 Comp. 11-11-55 IP 203 BOPD


Tops	Depth	Datum
Awk		+297
HEEB	3715	-1298
LANS	3755	-1338
B/KC	3988	-1571
TD	3995	-1578

Casing  
8" 180  
5" 3990

155'-160'

PERF 3910-15: 4 BOPH  
ACID 3000: 35 BOPH

HOLLEY POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS