

4-031759

9-24 15
15-665-01002-0006 R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1957

RT
KCL SE SE SE /4 SEC. 10 , 09 S, 24 W
660 330 feet from S section line
660 330 feet from E section line

Operator license# 6861 Lease Nickelson well # 1

Operator: Ron's Oil Operations County Graham

Address: R.R. 1 Well total depth 4032 feet 131.04
Box 194 Conductor Pipe: 0 inch @ 0 feet
Penokee, Kansas 67659 Surface pipe 8 5/8 Inch @ 180 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 24 Month: September Year: 92

Plugging proposal received from: Ron

Company: Ron's Oil Operations Phone:

Were: Order 300 sx. 65/35 pozmix - 10% gel.
Hole open by bailer.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:30A.M., Day: 24, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 180' w/100 sx. 5 1/2" set @ 4031'
w/150 sx. Perf. 3837' - 3965'. Shots @ 2100' - 1250' recovered 675' -
5 1/2" casing. Pumped bottom plug with 110 sx. Shot off, circulated
cement to surface with total of 270 sx. cement with 500# hulls mixed
in. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

10-8-92
OCT 8 1992

Remarks: Condition of casing(in hole): GOOD X BAD Anhy. plug: YES 2130 NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2466 GL

CONSERVATION DIVISION
Wichita, Kansas

I did[X] / did not[] observe the plugging.

Carl Goodrow

(agent)

INVOICED

DATE 10-20-92

WV NO 36511