

15-065-20684-0000

To: 6 030894
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-11-26-74

NE NW NE, SEC. 10, T 9 S, R 24 (W)E

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718

Lease Name Clark Well # 5

Operator: Fell Oil and Gas Co.

County Graham 130.13

Name & Address: Box 9487

Well Total Depth 4004 feet

Tulsa, Ok. 74157

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 175'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Kansas

Company to plug at: Hour: _____ Am _____ Day: 4 Month: 6 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) _____

were: 8 5/8 set @ 175 Cwc. 4 1/2" set at 4004 w/ 105 sx Toc 3475

Perf 3801' - 3925 order sand & Com cmt. Pull pipe order

200 sx ATL 65/35 poz 10% gel 2% dicel cmt. blend 6 sx hull

Allied Cmt. Co. Wellbrock Water Trucks

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 AM Day: 4 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand to 3750' w/ 5 sx com cmt. on Sand w/bailer.

3 shots @ 2100' 1400' and 1200' recovered 1200' of 5 1/2 casing.

mix and pump down 8 5/8" 200 sx ATL blend w/ 6 sx hulls.

Max. PSI 300# close in 150 # plug complete.

RECEIVED
STATE CORPORATION COMMISSION
7-16-87
JUL 16 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Very little stretch. Pipe held by formations
(If additional description is necessary, use BACK of this form.)

INVOICED (date of invoice) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 7-20-87
INV. NO. 17521