

15-065-02872-0000

To: 6 030893
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW NE NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718

Lease Name Clark Well # 3

Operator: Fell Oil and Gas Co.
Name & Address Box 9487
Tulsa, Ok. 74157

County Graham 129.64
Well Total Depth 3989 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Chase, K.s

Company to plug at: Hour: PM Day: 4 Month: 6 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) _____

were: 8 5/8 set @ 308' w/250'sx 5 1/2 set @ 3989' w/ 150 sx Toc 3200

Perf. 3816' - 3934' order sand and com. Cmt. Pull pipe order 200 sx ATL

65/35 poz 10% gel 2% dicel blend 6 sx hulls Allied Cmt. Co.

Wellbrock Water Trucks

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 PM Day: 4 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand to 3750' w/ 5sx com. cmt. on sand w/bailer 2 shots @

1400' and 1200' recovered 1200' of 5 1/2" csg. Mix and pump down 8 /58"

175 sx ATL blend w/ 6 sx hulls Max. PSI 900 # close in 400 # Plug Complete.

RECEIVED
STATE CORPORATION COMMISSION
7-16-87
JUL 16 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Very little stretch pipe held tightly by formation
(if additional description is necessary, use BACK of this form.)

INVOICED
(if applicable) observe this plugging.

DATE 7-20-87

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 17522

Carl Goodrow