

15-065-02871-0000

To: 6 030892  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 8-5-55

SE NW NE, SEC. 10, T 9 S, R 24 W/E  
4290 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718

Lease Name Clark Well # 2

Operator: Fell Oil and Gas. Co.

County Graham 131.37

Name & Address

Box 9487

Well Total Depth 4042 feet

Tulsa, Ok. 74157

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 303'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Kansas

Company to plug at: Hour: \_\_\_\_\_ PM Day: 4 Month: 6 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 8 5/8 set @ 303' Cuc. 5 1/2" set at 4040' w/ 105 sx toc 3504'

Perf. 3937 - 3976' order sand and com cmt. Pull pipe order

200 sx ATL 65/35 poz 10% gel 2% Dicol cmt. blend. 6 sx hulls Allied Cmt. Co.

Wellbrock Water Trucks.

Plugging Proposal Received by Carl Goodrow Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 PM Day: 4 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand to 3880' w/5 sx com. cmt. on sand w/bailer

2 shots at 1400' and 1200' recovered 1200' of 5 1/2" csg.

mix and pump down 8 5/8" 200 sx ATL blend w/ 6 sx hulls

Max. PSI 300# close in at 150 # Plug Complete

RECEIVED  
STATE CORPORATION COMMISSION  
7-16-87  
JUL 16 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-20-87  
INV. NO. 17524

Signed Carl Goodrow (TECHNICIAN)