

15-065-02870-0000

6 030891

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-7-17-55

NW NW NE, SEC. 10, T 9 S, R 24 W/E

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718

Lease Name Clark Well # 1

Operator: Fell Oil and Gas Co

County Graham 130.98

Name & Address Box 9487

Well Total Depth 4030 feet

Tulsa, OK. 74157

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 291'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050

Address Chase Kansas 67524

Company to plug at: Hour: AM Day: 4 Month: 6 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone)

were: 8 5/8 set @ 291' cuc 5 1/2 set @ 4031' w/ 150 sx toc 3310'

Perf 3845' - 3984' order sand and Com. Cmt. Pull pipe

order 200 sx ATL 65/35 poz 10% gel 2% Dicel 6 sx hulls Allied Cmt. Co.

Wellbrock Water Trucks

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 8:45 AM Day: 4 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand to 3790' w/ 5 sx com Cmt. on sand w/ bailer

2 shots at 1400' and 1200' recovered 1200' of 5 1/2"

Mix and pump down 8 5/8" 175 sx ATL blend w/ 6 sx hulls

Max, PSI 600 # close in 300 # Plug Complete

RECEIVED STATE CORPORATION COMMISSION 7-16-87 JUL 16 1987 CONSERVATION DIVISION Wichita, Kansas

Remarks: Very little stretch pipe held tightly in hole by formations (if additional description is necessary, use BACK of this form.)

INVOICED (if did not) observe this plugging.

DATE 7-20-87

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INV. NO. 17520