

8-17-92 15-065-02663-0001
4-041448

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 5-26-57

C SW SW /4 SEC. 11, 09 S, 24 W
feet from S section line
feet from E section line

Operator license# 6931

Lease Rice Estate well # 1

Operator: Bowman Oil Company

County Graham

Address: Box 17
Codell, Kansas 67630

Well total depth 4074 ^{RT} 132.76 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 234 feet
w/130 sx.

Aband. oil well X ^{KCCRT} Gas well , Input well , SWD X, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 7 Month: August Year: 92

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone:

Were: 5 1/2" casing set @ 4037' w/50 sx. cement. Perf. @ 3860'-4000'.
Perf. @ 1980'. Dakota @ 1300'. Top of tubing fish 1990'.
Ordered 300 sx. common cement with 1/4# flocele plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M., Day: 17, Month: August, Year: 92

Actual plugging report: R.I.H. with tubing to top of fish @ 1990'.
Spot 100 sx. common with 1/4# flocele in cement. Pull tubing to 1250'.
Spot 100 sx. cement to circulate cement at surface. Pull tubing squeeze
100 sx. cement with 200# hulls. Max. 500#. S.I. 300#. Hooked-up
to 8 5/8 casing. Squeeze 100 sx. 60/40 pozmix - 10% gel. with 1/4#
flocele with 100# hulls. Max. 500#. S.I. 500#.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1993

4-12-93
CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 2480 GL

I did X / did not observe the plugging.

Dennis L. Hamel

DATE 4-14-93
INVOICE NO 37562

HD.

(agent)
Form CP-2/3

8-17-92