

9-2-87

6 030945

API NUMBER 15- 065-22,396-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NE, SEC. 13, T 9 S, R 24 W/E
3640 feet from S section line
1820 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6861

Operator: Ron's Oil Operations
Name & Address: Box 112
Penokee, Kansas 67659

Lease Name Nicholson Well # 13-2
County Graham 130.33
Well Total Depth 4010 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Western Kansas Drilling License Number 8241
Address Hays, Kansas 67601

Company to plug at: Hour: AM Day: 2 Month: Sept Year: 19 87

Plugging proposal received from John Tremble
(company name) Western Kansas Drilling (phone)

were: 8 5/8" set at 261' w/165 sks Cwc. Circulate hole w/no less than 36 vis. mud
with no los or gain of hole fluids. Displace cement plugs with drill pipe.

Balance all plugs with mud. Order 190 sks 60/40 Pozmix 6% Gel 3% Ca Cl Cement
Blend with 8 5/8" w.p. Allied Cement Company.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 AM Day: 2 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT

With drill pipe displace 25 sks at 2075'
100 sks at 1200' w/1 sk Hulls
40 sks at 300'
10 sks at 40' w/ w.p. to Kelly depth
15 sks in rat hole with pipe circ. to flow depth.

Remarks: Anhy 2075' Elev. 2420'
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
9-25-87
SEP 25 1987

INVOICED

observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 9-29-87

INV. NO. 18310

Carl Goodrow

09-02 OCT 2 9 1987 DEC 0 3 1987