

6 030718

201-R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21, 137-0000

SWNEW, SEC. 13, T 9 S, R 24 (W)

4290 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6861

Lease Name HILDEBRAND Well # "A" 1

Operator: RON'S OIL OPERATING INC.

County GRAHAM 141.23

Name & Address RT. 1, BOX 112

Well Total Depth 4035 feet

PENOKEE, KANSAS

Conductor Pipe: Size _____ feet

67659

Surface Casing: Size 8 3/8 feet 226'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS 67524

Company to plug at: Hour: PM Day: 17 Month: 4 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING (phone) _____

were: 8 3/8 @ 226' w/180sx. 4 1/2 @ 4008 w/150sx. BERF 3800'-54' 3902'

ORDER SAND&COM.CMT. PULL PIPE ORDER 250SX. (ECONOLITE) THRIFTY

MIX. 16SX. HULLS BJ TITAN WELBROCK WATER TRUCK.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 17 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT DUMP SAND TO 3800' SPOT 4SX. COM.CMT. ON SAND

W/BAINER SHOT & RECOVERED 1840' OF 4 1/2"

HOOK ON TO 8 3/8 MIX & PUMP 4SX. HULLS 250SX THRIFTY MIX + 2SX. HULLS

MAX. PSI 300# CLOSE IN 300# Plug. COMPLETE

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1986 4-28-86

Remarks: _____
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(did / did not) observe this plugging.

DATE APR 29 1986

Signed Carl Goodrow
(TECHNICIAN)

18
4-25-86

INV. NO. 13599