

4-032043

1-12

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-21,546-0000

NW NE NE /4 SEC. 13, 09 S, 24 W
4950 feet from S section line
990 feet from E section line

Operator license# 6861

Lease Hildebrand well #B-1

Operator: Ron's Operations, Inc.

County Graham

Address: R.R. 1 - Box 194
Penokee, Kansas 67659

Well total depth 4015 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

130.49

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 12 Month: January Year: 95

Plugging proposal received from: Richard

Company: Mike's Testing & Salvage Phone:

Were: Order 200 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:45P.M., Day: 12, Month: January, Year: 95

Actual plugging report: 8 5/8" set at 250' w/150 sxs.cwc. 4 1/2" set at 4014' w/175 sxs. Prod. perfs. 3843' - 3995'. P.B.T.D. 3955'. Sanded back to 3790' with 4 sxs. common cement on sand with bailer. Shots at 2000' - 1500' - 1250'. Displaced 55 sxs. cement blend with 500# hulls from 700' to 2000'. Shot free at 617' - pulled to 250' circulation with 55 sxs. cement blend - lay down casing - topped off 8 5/8" w/15 sxs. cement blend. Plug complete.

RECEIVED
CONSERVATION COMMISSION
JAN 30 1995
1-30-95
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks:

Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES , CALC X, NO Dakota plug:YES X NO
Plugged through TUBING , CASING X. Elevation: GL

I did X / did not [] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

INVOICED

DATE 2-1-95

INV. NO. 42121

1-12