

15-065-01614-000113
9-24
R
4-031760

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E-10,367
API number: 15- - 1957

C SE NE /4 SEC. 15, 09 S, 24 W
3300 feet from S section line
660 feet from E section line

Operator license# 6861

Lease Nickelson well #A#2

Operator: Ron's Oil Operations

County Graham

Address: R.R. 1
Box 194
Penokee, Kansas 67659

Well total depth 4055 feet ^{131.78}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well , Gas well , ^{FNHR} Input well X, SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 24 Month: September Year: 92

Plugging proposal received from: Ron

Company: Ron's Oil Operations Phone:

Were: Order 150 sx. 65/35 pozmix - 10% gel.
Hole open to bottom.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:30 P.M., Day: 24, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 217' w/175 sx. 5 1/2" set @ 4055'
w/100 sx. Squeezed @ 2730' cwc. 2" tubing cemented in 5 1/2" from
3900' to surface. Perf. 3980' - 4022'. Squeezed 2" tubing with 70 sx.
cement blend to Max. P.S.i. 500#. Close in P.S.I. 200#. Squeezed
8 5/8" with 50 sx. cement blend to Max. P.S.I. 200#. Close in P.S.I.
150#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES 2136 NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING X. Elevation: 2485 GL

I did X did not[] observe the plugging.

Carl Goodrow

DATE 10-20-92

(agent)

INV. NO. 36512

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
10-8-92
OCT 8 1992

CONSERVATION DIVISION
Wichita, Kansas