



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 27 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rine of Petroleum Management, Inc. has this date requested permission to plug the following described well:

Mr. Rine guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated.

Complete Address: 1515 KSB&T Building, Wichita, Kansas.

Lease Name: Holly Unit Well No. 16-2

Location: NE-NE-NW <sup>SW</sup> Sec. 5 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4035' Oil Well

Gas Well  Input Well X SWD Well  D & A  Lost Hole

Mr. Rine was instructed to plug the well as follows:

232'--8 5/8" Surface casing, cement circulated.

4021'--4 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3985'. Top perforations from 3956' to 3962.

Sand well back to 3930' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*W. L. Nichols*

Conservation Division Agent