



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rine of Petroleum Management, Inc., has this date requested permission to plug the following described well:

Mr. Rine guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated.

Complete Address: 1515 KSB&T Building, Wichita, Kansas.

Lease Name: Holly Unit Well No. 17-1

Location: NE-NE-SE Sec. 5 Twp. 9 Rge. (E)(W) 2h

County: Graham Total Depth 4070' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Rine was instructed to plug the well as follows:

232'--8 5/8" Surface casing, cement circulated.
4069'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 4024'. Top perforations from 3987' to 4012'. Well has been squeezed @ 1355' with 100 Sx. cement.

Sand well back to 3960' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent