

15-065-00848-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

1-20-72
JAN 20 1972

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of SouthWest Casing Pulling, Inc has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Holly Unit-Tract 12 Well No. 1

Location: NW-NW-NW Sec. 6 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4042' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

187'--8 5/8" Surface casing cement circulated.

4036'--5 1/2" Production casing cemented on bottom with 75 Sx. No Plug-back. Top perforation @ 3850'.

Sand well back to 3800' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

A. L. Nichols
Conservation Division Agent