

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 4-10-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling Co., has this
date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Robert McKinley Well No. 5

Location: NW-SE-NE Sec. 6 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 3969' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

320'--9 5/8" Surface casingm cement circulated with 325 Sx.
3969'--5 1/2" casing cemented on bottom with 100 Sx. Well plugged back to
3931'. Top of perforations @ 3783'. DV Tool set @ 2157 with 125 Bbl.
Chem-Pak. Unfishable junk @ 3250'.

Push plug to top of junk @ 3250', sand well back from 3250' to 3225' and
set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with
7 sacks hulls, 40 sacks gel and 200 Cu. Ft. cement and stage material.

Very truly yours,

M. L. Dichele
Conservation Division Agent