

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
4-10-72
APR 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Robert McKinley Well No. 4

Location: SE-NE-NE Sec. 6 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 3956' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

900'--8 5/8" Surface casing, cement circulated with 510 Sx.
3948'--5 1/2" casing cemented on bottom with 100 Sx. Top perforations from
3873' to 3875'. DV Tool @ 2171' with 80 Bbl. Chem-Pak.

Push plug to 3850', sand well back to 3825' and set 5 Sx. cement with dump
bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel
and 120 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent