

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
4-10-72
APR 10 1972

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Robert McKinley Well No. 2

Location: SE-NW-NE Sec. 6 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 3956' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

310'--10 3/4" Surface casing, cement circulated with 210 Sx.
3951'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool
@ 2188' with 150 Bbl. Chem-Pak. Well plugged back to 3946', top perfor-
ations @ 3917'.

Sand well back to 3890' and set 5 Sx. cement with dump bailer. Pull 7"
casing and squeeze well with 7 sacks hulls, 40 sacks gel and 200 Cu. Ft.
cement, staged.

Very truly yours,

Conservation Division Agent