



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mickelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Don Pratt Oil Operations,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Ron Nickelson Well No. 1

Location: NW-NW-SE Sec. 13 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 3765' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Mickelson was instructed to plug the well as follows:

169'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.  
cement thru DP. Pull DP to 185' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
9-11-70  
SEP 11 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

M. L. Deibel  
Conservation Division Agent