

15-065-20218-0000

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mikelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mikelson guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Hildebrand Well No. A-1

Location: NE-NE-NW Sec. 13 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4020' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Mikelson was instructed to plug the well as follows:

184'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 100 Sx.  
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1969 Very truly yours,  
CONSERVATION DIVISION  
Wichita, Kansas

M. L. Mikelson  
Conservation Division Agent