

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Company, has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Nickelson Well No. 4-W

Location: CSW-NE Sec. 15 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4048 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Blandin was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated.
4048'--5 1/2" casing cemented on bottom with 100 Sx. Well plugged back to
3940' top perforations @ 3863'. Hole in 5 1/2" casing @ 1160'.

Run 2" tubing to bottom and displace 35 Sx. cement thru tubing. Squeeze
5 1/2" casing thru hole @ 1160' with 100 Sx. cement displacing with water.
Pull 5 1/2" casing and squeeze hole with 5 sacks hulls, 30 sacks gel and
130 Sx. cement staged

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1969

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

[Signature]
Conservation Division Agent