

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wilber Crandall of Knight Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Crandall guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Nickelson Well No. 1

Location: SW-NE-SW Sec. 14 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4045 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Crandall was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated.  
4044'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 4015'. Top perforations from 3988' to 3991'.

Sand well back to 3950' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 30 Sacks gel plus 5 sacks hulls and 130 Sx. cement staged.

RECEIVED  
STATE CORPORATION COMMISSION  
10-7-68  
OCT 7 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

W. L. Nichols  
Conservation Division Agent