



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
7-26-71
JUL 26 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Nernberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Nernberger guarantees payment of the plugging fee.

Operator's full Name: Murfin-Kantor & Executive,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Nickelson Well No. C-2

Location: SE-NW-SE Sec. 11 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 3975' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nernberger was instructed to plug the well as follows:

172'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.
cement thru DP. Pull DP to 185' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

R. L. Nichols
Conservation Division Agent