

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
4-25-66
APR 25 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Dellinger of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Petroleum Explorations, Inc.

Mr. Dellinger guarantees payment of the plugging fee.Operator's full Name: Petroleum Explorations, Incorporated,Complete Address: 6210 West 10th, Topeka, Kansas.Lease Name: Nickelson Well No. 1Location: CSW-SE Sec. 14 Twp. 9 Rge. (E) (W) 24County Graham Total Depth 3988 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Dellinger was instructed to plug the well as follows:

186'--8 5/8" Surface pipe, cement circulated.
3988'--4 1/2" Production casing cemented with 120 Sx. Well
plugged back to 3956'. Top perforations @ 3826 1/2'.

Push plug to 3800', sand to 3750' and set 3 Sx. cement with
dump bailer. Pull 4 1/2" to 600' and circulate heavy gel mud.
pull 4 1/2" to 540' and displace 20 Sx. cement thru 4 1/2". Pull
4 1/2" to 180' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2"
set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent