



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
2-7-74  
FEB 7 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Smith of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: F. & M Oil Company.

Complete Address: 603 Union Center Building, Wichita, Kansas.

Lease Name: Nickelson Well No. 1

Location: SE-SE-NW Sec. 11 Twp. 9 Rge. (E)(W)24

County: Graham Total Depth 4000' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Smith was instructed to plug the well as follows:

185'--8 5/8" Surface casing, cement circulated.

3999'--5 1/2" Production casing cemented on bottom iwth 100 Sx. Top of cement @ 3430'. No plug-back indicated. Top perforations from 3842-45'.

Push plug to 3800', sand back to 3750' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent