

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 27 Twp. 9S Rge. 24W(E) (W)

Location as "NE/CNW/SW" or footage from lines. SE NE NE

Lease Owner Rock Island Oil & Refining Co.

Lease Name Boone Well No. 1

Office Address 321 W. Douglas Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed September 13, 1966

Application for plugging filed September 13, 1966

Application for plugging approved September 13, 1966


Plugging commenced September 13, 1966

Plugging completed September 13, 1966

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4075 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 206' | -0- |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug & 20 sx cement @ 540'. Heavy mud to 210' 1/2 sx hulls & plug. 20 sx cement dry - heavy mud to 40' - 1/2 hull & 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
9-20-66
SEP 20 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company

Address Box 173 - Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Maxine V. Starr (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Maxine V. Starr

1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of September, 19 66

Jean Stollar
Notary Public.

My commission expires 5-22-70



DRILLING LOG

No. 1 Boone

CASING RECORD:

8 5/8" @ 205'
w/140 sx cement

COMPANY: Beck Island Oil & Refining Co.

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: September 9, 1966

COMPLETED: September 13, 1966

DESCRIPTION:

SE NE NE
27-08-24W
Graham Co., Ks.

ELEVATION:

TOTAL DEPTH: 4075'

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|------------------|-------------|-----------|----------------|
| Shale | 0 | 1760 | |
| Sand | 1760 | 1880 | |
| Shale | 1880 | 2137 | |
| Anhydrite | 2137 | 2176 | |
| Shale | 2176 | 2480 | |
| Shale & Lime | 2480 | 3575 | |
| Lime | 3575 | 4075 | |

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 15th day of September, 1966.

Jean Hollas
Notary Public

My Commission Expires:

5-23-70

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1966
CONSERVATION DIVISION
WICHITA, KANSAS

