


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Graham County. Sec. 27 Twp. 9S Rge. (E) 24 (W)  
Location as "NE/CNW%SW%" or footage from lines C SW NW  
Lease Owner Chief Drilling Co., Inc.  
Lease Name MOORE Well No. 1  
Office Address Box 797 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7/25 1963  
Application for plugging filed 7/25 1963  
Application for plugging approved 7/25 1963  
Plugging commenced 7/25 1963  
Plugging completed 7/25 1963  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols - Moreland, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4067 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	202	8-5/8"	7/18/63	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set wooden plug @ 550' with 20 sacks cement thru drill pipe  
Mixed with 1/3 sack hulls  
Set wooden plug @ 180' with 20 sacks cement thru drill pipe  
Mixed with 1/2 sack hulls  
Set wooden plug @ 40' with 10 sacks cement thru drill pipe

RECEIVED  
STATE CORPORATION COMMISSION  
7-29-63  
JUL 29 1963

CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc.  
Address Box 797 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 797 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 1963  
My commission expires Jan 26, 1967  
Carmen R. Cook  
Carmen R. Cook, Notary Public.



WELL LOG

Chief Drilling Co., Inc.  
Box 797  
Great Bend, Kansas

MOORE #1  
C SW NW Sec. 27-9S-24W  
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 7-18-63  
Completed: 7-25-63

Casing Record: 8-5/8" @ 202' w/150 sacks Sunset Cement.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & Shale	0	100	2511 Gr.
Shale	100	1710	2513 D.F.
Sand	1710	1900	2516 K.B.
Shale & Red Bed	1900	2167	
Anhydrite	2167	2200	
Shale & Shells	2200	2595	
Shale, Shells & Lime Streaks	2595	2815	
Lime & Shale	2815	2960	
Lime	2960	3100	
Lime & Shale	3100	3360	
Lime	3360	4067	
Total Depth	4067		

<u>FORMATION TOPS</u>			
Anhydrite	2167	+	349
Heebner	3822	-	1306
Toronto	3843	-	1327
Lansing	3857	-	1341
Total Depth	4067	-	1551

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW NW Sec. 27-9S-24W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 26th day of July, 1963.

*Carmen R. Cook*  
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.



**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 29 1963

CONSERVATION DIVISION  
Wichita, Kansas