

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-20,109 - 0000

LEASE NAME Moore

WELL NUMBER 1

SPOT LOCATION NW SW SW

SEC. 27 TWP. 9 RGE. 24 (E) or (W)

COUNTY Graham

Date Well Completed 2/29/68

Plugging Commenced 4/25/84

Plugging Completed 4/25/84

LEASE OPERATOR Ron's Oil Operations

ADDRESS RFD 1 Box 112, Penokee, Kansas 67659

PHONE # (913) 674-2315 OPERATORS LICENSE NO. 6861

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Carl Goodrow

Is ACO-1 filed? N/A If not, is well log attached? \_\_\_\_\_

Producing formation Lansing-Ks. City Depth to top 4036 bottom 4054 T.D. 4132

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	208	None
				4 1/2	4130	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Mixed & pumped 60 s x s with 3 hulls, 18 s x s gel down casing & 44 sxs of cement on top. Pressured up to 1,000 lbs. Shut in at 300 lbs. Hooked up to annulus & mixed 50 sxs cement, and pumped in. Shut in at 150 lbs. Plugged down at 3:15 P.M. All cement was 50/50 poz with 6% salt & 3% C.C.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pfeifer-Sharpe, Inc. License No. 6967  
Address East Hwy. 24, P. O. Box 386, Hill City, Kansas 67642

STATE OF Kansas COUNTY OF Graham, ss.


Bill Daily (employee of operator) or  
(~~XXXXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Daily

(Address) Box 386 Hill City, Kansas 67642

SUBSCRIBED AND SWORN TO before me this 16 day of May, 1984

Debra L. Pfeifer-Wente  
Notary Public



My Commission expires: May 12, 1986

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 21 1984  
5-21-84  
CONSERVATION DIVISION  
Wichita, Kansas