

15-065-00456-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 25 Twp. 9S Rge. 24 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Lohmann-Johnson Drilling Co., Inc & Kennard Oil Co Inc
Lease Name Pettett Heirs Well No. 1
Office Address 320 Indiana Bank Building, Evansville, Indiana
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 18, 1954
Application for plugging filed August 18, 1954
Application for plugging approved August 18, 1954
Plugging commenced August 18, 1954
Plugging completed August 18, 1954
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4495 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4495 to 200 - Heavy Mud & 15 sks cement on top of plug
200 to 40 - Mud
40 to 0 - 1/4 Sk Hulls on Plug and 10 Sacks Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oilwell Cementing Company
Address Plainville, Kansas

STATE OF Indiana, COUNTY OF Vanderburgh, ss.
J. B. Lohmann (employee or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lohmann-Johnson Drilling Co., Inc.

By [Signature] 320 Indiana Bank Building, Evansville, Indiana

SUBSCRIBED AND SWORN TO before me this 24th day of August, 1954

My commission expires November 5, 1957

[Signature] Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
8-26-54
AUG 26 1954

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 25 T 9 R 24 W
BOOK PAGE 58 LINE 3

PETTETT HEIRS NO. 1

SE SE NW - Section 25-10S-24W

Graham County, Kansas

WELL RECORD

Operator: Lohmann-Johnson Drilling Co., Inc. and Kennard Oil Company, Inc.
 320 Indiana Bank Building
 Evansville, Indiana

Contractor: Lohmann-Johnson Drilling Co., Inc.
 320 Indiana Bank Building
 Evansville, Indiana

Casing: Ran 10 Jts. 8-5/8" Surface Pipe set @ 215' W/150 Sacks

Started: August 3, 1954
 Completed: August 19, 1954

RT
KCC LOG

FROM	TO	FORMATION
0	95	Shale
95	120	Sand
120	215	Shale
215	1115	Shale
1115	1175	Lime
1175	1530	Shale & Lime Streaks
1530	1600	Shale & Shells
1600	1860	Sand
1860	2125	Shale - Shells
2125	2135	Shale
2135	2175	Anhydrite
2175	2430	Shale & Shells
2430	2775	Lime & Shale
2775	2860	Lime
2860	2915	Shale & Lime
2915	2960	Lime
2960	2975	Shale & Lime
2975	3050	Lime & Shale
3050	3100	Shale
3100	3160	Lime & Shale
3160	3275	Shale & Shells
3275	3350	Shale
3350	3415	Shale & Lime
3415	3535	Lime & Shale
3535	3635	Shale & Lime
3635	3840	Lime & Shale
3840	4050	Lime
4050	4189	Lime & Shale
4189	4218	Conglomerate
4218	4255	Shale & Lime
4255	4348	Lime & Shale
4348	4362	Shale & Lime
4362	4412	Chert
4412	4450	Shale & Lime
4450	4475	Lime & Shale
4475	4495	Arbuckle
4495		TOTAL DEPTH

Dry and Abandoned
 Plugged August 18, 1954

PLUGGING

FILE SEC 25 T 9 R 24 W
 BOOK PAGE 51 LINE 3

The undersigned, Lohmann-Johnson Drilling Company, Inc., hereby certifies that the above Log is a true and correct log of the formations encountered in drilling the above Well as reflected by the Daily Drilling Reports.

Subscribed and sworn to before me this 24th day of August, 1954

LOHMANN-JOHNSON DRILLING CO., INC.

By *Joe Lohmann*

RECEIVED
 AUG 26 1954
 DIVISION
 WICHITA, KANSAS