

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-01000-00-00
API NUMBER comp 6-57
LEASE NAME HOETING (DREILING)

TYPE OR PRINT

WELL NUMBER 5-1

NOTICE: Fill out completely 330 Ft. from S Section Line
and return to Cons. Div. 2970 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC. 28 TWP. 9S RGE. 24W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY GRAHAM
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 6-26-57
Character of Well OIL(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 9/17/02
Plugging Completed 9/17/02

The plugging proposal was approved on 9-17-02(date)
by Dennis Hamel @ KCC in Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? _____
Producing Formation LKC Depth to Top 3864 Bottom 4048 TD 4110' Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	205'	8 5/8	205	0
		production	4107	5 1/2"	4107	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Perf 5 1/2" csg. 2100' & 1100'; pumped 200 sxs 60-40 poz 10% gel 400# hulls to circ. cmt to surf. Tied onto 5 1/2 csg. Pumped 40 sxs. Max press. 400#, ISIP 300#. Tied on to 8 5/8" csg. Pumped 35 sxs & 100# hulls, max press 300#, ISIP 100#. P&A Approved and witnessed by Dennis Hamel w/KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of Oct. 2002

Notary Public - Barbara J. Dodson

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED
10-9-02
OCT 09 2002
KCC WICHITA

Handwritten initials

15-065-01000-0000

ALLIED CEMENTING CO., INC. 11733

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>9-17-02</u>	SEC.	TWP.	RANGE	CALLED OUT <u>8:00 AM</u>	ON LOCATION <u>10:00 AM</u>	JOB START	JOB FINISH <u>12:30 PM</u>
LEASE <u>Hoeting</u>		WELL # <u>5-1</u>		LOCATION		COUNTY <u>Graham</u>	STATE <u>K</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR C. Todd's

TYPE OF JOB Plug

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2 3/8 DEPTH 2200

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED
275 lbs 6940-10906el
500 # HULLS

COMMON	<u>165</u>	@	<u>665</u>	<u>1097.25</u>
POZMIX	<u>110</u>	@	<u>355</u>	<u>390.50</u>
GEL	<u>19</u>	@	<u>10.18</u>	<u>190.82</u>
CHLORIDE		@		
<u>Hulls</u>	<u>5</u>	@	<u>18.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>275</u>	@	<u>1.10</u>	<u>302.50</u>
MILEAGE	<u>44/51</u>	@	<u>1.10</u>	<u>605.00</u>

TOTAL 2675.25

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Bill</u>
# <u>177</u>	HELPER <u>Darin</u>
BULK TRUCK	
# <u>361</u>	DRIVER <u>LONNIE</u>
BULK TRUCK	
# _____	DRIVER _____

REMARKS:

Tubing c 2201 - cement w/ 200 lb
Cement w/ 400 # HULLS, Circ. to screen
pump down csg w/ 40 lb
Max 400 # 300 # SHUT FR

pump down Ann w/ 35 ph w/ 100 #
Max 300 # 100 # SHUT FR HULLS

SERVICE

DEPTH OF JOB	_____
PUMP TRUCK CHARGE	<u>475.00</u>
EXTRA FOOTAGE	@ _____
MILEAGE	<u>55</u> @ <u>3.00</u> <u>165.00</u>
PLUG	@ _____
	@ _____
	@ _____

RECEIVED

OCT 09 2008

TOTAL 640.00

CHARGE TO: MURFIN

STREET _____

CITY _____ STATE _____ ZIP _____

KCC WICHITA FLOAT EQUIPMENT

_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE John Gust

PRINTED NAME _____

ALLIED CEMENTING CO., INC.

P.O. BOX 34
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566

RECEIVED

SEP 23 2002

Invoice Number: 088122

Invoice Date: 09/20/02

15-065-01000-0000

 * INVOICE *

COPY

Sold Murfin Drilling Co.
 To: 250 N. Water, St. #300
 Wichita, KS
 67202

Cust I.D.....: Murfin
 P.O. Number...: Hoeting 5-1
 P.O. Date.....: 09/20/02

Due Date.: 10/20/02
 Terms.....: Net 30

36
 BA/RK

Item I.D./Desc	Qty	Used	Unit	Price	Net	TX
Common	165.00		SKS	6.6500	1097.25	T
Pozmix	110.00		SKS	3.5500	390.50	T
Gel	19.00		SKS	10.0000	190.00	T
Hulls	5.00		SKS	18.0000	90.00	T
Handling	275.00		SKS	1.1000	302.50	T
Mileage (55)	55.00		MILE	11.0000	605.00	T
275 sks @\$.04 per sk per mi						
Plug	1.00		JOB	475.0000	475.00	T
Mileage pmp trk	55.00		MILE	3.0000	165.00	T

All Prices Are Net, Payable 30 Days Following
 Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$ 331.53
 ONLY if paid within 30 days from Invoice Date

Subtotal:	3315.25
Tax.....:	225.44
Payments:	0.00
Total....:	3540.69