

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
67202 TYPE OR PRINT

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-20339-00-00  
LEASE NAME HOETING Wichita, KS

RECEIVED  
4-14-03  
APR 14 2003

WELL NUMBER 1-1  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

2970 Ft. from S Section Line  
4950 Ft. from E Section Line

KCC WICHITA

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC 28 TWP. 9S RGE. 24W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

COUNTY GRAHAM

PHONE # (316 ) 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 4/2/03 KCC 2-T

Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 4/2/03

Plugging Completed 4/2/03

The plugging proposal was approved on 4/2/03 (date)  
by Darrel Dipman w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? ? If not, is well log attached? no

Producing Formation LKC Depth to Top 3924 Bottom 4084OA TD 4155 PBD 4110'

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	238	8 5/8	288	0
		Prod	4147'	4 1/2"	4147'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged well as follows: Perforated 4 1/2" csg. @2225 & 1075'. FL 300' f/surface. RIH w/2 3/8" tbg. To 2949. Pumped 80 sxs. 60-40 poz 10%gel, 300# hulls w/ full circ. Pulled tbg. To 1222'. Pumped 60sxs 100# hulls to circ cmt to surface. Tied onto 4 1/2" csg. Pumped 70 sxs max press. 700#. ISIP 200#. Tied onto 8 5/8". Pumped 75 sxs 100#hulls max press 100# ISIP 50#. Well P/A. Witnessed and approved by Darrel Dipman w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this     day of April, 2003

Notary Public - Barbara J. Dodson [Signature]



Form CP-4 Revised 05-88

[Signature]

# L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

28-9-24W  
SW SW NW

AUG 1 1970

## WELL LOG

15-005-20339-0000

Company Don E. Pratt Oil Operations  
P. O. Drawer 370  
Hays, Kansas 67601

Sec. 28 Twp. 9 Rng. 24 W

Farm Hoeting No. 1

Location SW SW NW

Total Depth 4155'

County Graham

Comm. 6-10-70 Comp. 6-17-70

Elevation: 2551' K. B.

2548' D. F.

2546' G. R.

Contractor L. J. Dreiling & Sons, Inc.  
Victoria, Kansas 67671

Production:

Casing Record

Cement Record

230' - 8 5/8"  
4147' - 4 1/2"

150 sac ka cement  
200 sacks cement

P 135 BOPD + 25% with  
LKC  
GR 42.2

Figures Indicate Bottom of Formations

0'	135'	Top Soil & Sand
135'	160'	Sand
160'	165'	Iron ✓
165'	190'	Gravel
190'	238'	Blue Shale
238'	1150'	Shale & Sand
1150'	1765'	Shale & Sand
1765'	1975'	Sand
1975'	2015'	Redbed & Shale
2015'	2210'	Shale
2210'	2250'	Anhydrite
2250'	2505'	Shale
2505'	2880'	Shale with Lime Streaks
2880'	3124'	Lime & Shale
3124'	3403'	Shale
3403'	3590'	Lime & Shale
3590'	3728'	Lime
3728'	3862'	Lime
3862'	3922'	Lime
3922'	3940'	Lime
3940'	3990'	Lime
3990'	4000'	Lime
4000'	4056'	Lime
4056'	4078'	Lime
4078'	4096'	Lime
4096'	4155'	Lime
4155'	T.D.	Lime



STATE OF KANSAS)  
)ss  
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Hoeting #1.

**ALLIED CEMENTING CO., INC.**

P.O. BOX 31  
 RUSSELL, KS 67665  
 PH (785) 483-3887  
 FAX (785) 483-5566

15-065-20339-0000

\*\*\*\*\*  
 \* I N V O I C E \*  
 \*\*\*\*\*

Invoice Number: 089637

Invoice Date: 04/08/03

Sold Murfin Drilling Co.  
 To: 250 N. Water, St. #300  
 Wichita, KS  
 67202

Cust I.D.....: Murfin  
 P.O. Number...: Noeting 1-1  
 P.O. Date.....: 04/08/03

Due Date.: 05/08/03  
 Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	171.00	SKS	7.1500	1222.65	T
Pozmix	114.00	SKS	3.8000	433.20	T
Gel	22.00	SKS	10.0000	220.00	T
Hulls	5.00	SKS	18.0000	90.00	T
Handling	285.00	SKS	1.1500	327.75	T
Mileage (54)	54.00	MILE	14.2500	769.50	T
285 sks @\$.04 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp trk	54.00	MILE	3.5000	189.00	T

All Prices Are Net, Payable 30 Days Following  
 Date of Invoice. 1 1/2% Charged Thereafter.  
 If Account CURRENT take Discount of \$ 372.71  
 ONLY if paid within 30 days from Invoice Date

Subtotal:	3727.10
Tax.....:	253.45
Payments:	0.00
Total...:	3980.55

RECEIVED  
 APR 14 2003  
 KCC WICHITA

# ALLIED CEMENTING CO., INC. 13314

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

2

DATE <u>4-2-03</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>10:00AM</u>	JOB START <u>10:30AM</u>	JOB FINISH <u>12:45PM</u>
LEASE <u>HOET...</u>	WELL# <u>1-1</u>	LOCATION <u>WAKEENEY N TO REDLINE</u>			COUNTY <u>GRAHAM</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>8W 42N</u>			

CONTRACTOR CO TOOLS

TYPE OF JOB PTA

HOLE SIZE	T.D.
CASING SIZE <u>4 1/2</u>	DEPTH
TUBING SIZE <u>2"</u>	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

OWNER \_\_\_\_\_

CEMENT

AMOUNT ORDERED 285 60/100 10% C.E.L.  
500# HULLS

COMMON	<u>171</u>	@	<u>7<sup>LS</sup></u>	<u>1222.65</u>
POZMIX	<u>114</u>	@	<u>3<sup>00</sup></u>	<u>507.45</u>
GEL	<u>22</u>	@	<u>10<sup>00</sup></u>	<u>433.20</u>
CHLORIDE		@		<u>270.00</u>
		@		
		@		
		@		
		@		
HULLS	<u>5</u>	@	<u>18<sup>00</sup></u>	<u>90.00</u>
		@		
		@		
		@		
HANDLING	<u>785</u>	@	<u>15</u>	<u>327.75</u>
MILEAGE	<u>50/SK/MILE</u>			<u>769.50</u>
TOTAL				<u>2348.15</u>
				<u>3063.10</u>

EQUIPMENT

PUMP TRUCK	CEMENTER	<u>MARK</u>
# <u>346</u>	HELPER	<u>ALAN</u>
BULK TRUCK		
# <u>362</u>	DRIVER	<u>RUFUS</u>
BULK TRUCK		
#	DRIVER	

REMARKS:

SERVICE

80 SKS C. 2900 w/300# HULLS  
60 SKS C. 1120 w/100# HULLS  
TREA ONTO 4 1/2 MIXED 70 SKS  
MAX PSE 700" SHUT IN 260"  
MIXED 75 SKS DOWN 8 5/8 w/100# HULLS  
MAX 100"  
SPLIT IN 50"

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 475.00

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE 54 @ 3<sup>50</sup> 189.00

PLUG @ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

TOTAL 664.00

CHARGE TO: MURFIN

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL \_\_\_\_\_

TAX \_\_\_\_\_

TOTAL CHARGE 3022.10 3727.10

DISCOUNT 10% IF PAID IN 30 DAYS

SIGNATURE John Gusto

PRINTED NAME