


15-065-60004-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 28 Twp. 9S Rge. (E) 24 (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Chief Drilling Co., Inc.
Lease Name SUPER Well No. 1
Office Address Box 797 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/11 1963
Application for plugging filed 6/11 1963
Application for plugging approved 6/11 1963
Plugging commenced 6/11 1963
Plugging completed 6/11 1963
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4086 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	204	8-5/8"	204	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set wooden plug @ 545'
Mixed 20 sacks cement through drill pipe
1/2 sack hulls and wooden plug set @ 195'
Mixed 20 sacks cement through drill pipe
1/2 sack hulls and wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
6-13-63
JUN 13 1963

Name of Plugging Contractor Chief Drilling Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address Box 797 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CHIEF DRILLING CO., INC.

(Signature) Richard Hoover
Box 797 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of June, 1963


My commission expires Jan. 26, 1967

Carmen R. Cook
Carmen R. Cook
Notary Public.

INVOICED

DATE 6/12/63

INV. NO. 7257-W



15-065-60004-0000

RECEIVED
STATE CORPORATION COMMISSION

WELL LOG

JUN 13 1963

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

SUPER #1
C SW NE Sec. 28-9S-24W
Graham County, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Contractor: Chief Drilling Co., Inc. Commenced: 6-3-63
Completed: 6-11-63

Casing Record: 8-5/8" @ 204' w/150 sacks Sunset Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand & Shale	0	203	2533 Gr.
Shale	203	1000	2535 D.F.
Shale & Shells	1000	1735	2538 K.B.
Sand	1735	1945	
Shale & Shells	1945	2179	
Anhydrite	2179	2224	
Shale & Shells	2224	2745	
Shale	2745	2945	
Lime & Shale	2945	3250	
Lime	3250	3335	
Lime & Shale	3335	3558	
Lime	3558	3640	
Lime & Shale	3640	3760	
Lime	3760	4086	
Total Depth	4086		

<u>FORMATION TOPS</u>	
Anhydrite	2179 + 359
Heebner	3837 -1299
Toronto	3861 -1323
Lansing	3875 -1337
Total Depth	4086 -1548

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW NE Sec. 28-9S-24W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.
V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 12th day of June, 1963.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.

