

15-065-02157-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 28 Twp. 9S Rge. 24W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Kohart "A" Well No. 2

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 26, 19 57

Application for plugging filed July 26, 19 57

Application for plugging approved July 26, 19 57

Plugging commenced July 26, 19 57

Plugging completed July 26, 19 57

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4110 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	7-13-57	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Filled hole with mud and set No. 1 plug at 210' with 20 sacks cement, filled hole to 40' and set No. 2 plug with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.  
Address 780 Fourth National Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P  
780 Fourth National Bldg., Wichita 2, Kansas (Address)



SUBSCRIBED AND SWORN to before me this 2nd day of August, 19 57

Quetta M. Duncan Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
8-3-57  
AUG 3 1957

PLUGGING  
FILE SEC 28 T 9 R 24 W  
BOOK PAGE 32 LINE 35

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
780 Fourth National Building  
Wichita 2, Kansas

Kohart "A" No. 2  
SW SW SE Sec. 28-9S-24W  
Graham County, Kansas

Total Depth: 4110'

Elevation: 2535' RB  
Production: D & A

Commenced: 7-13-57 Completed: 7-26-57

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 222' with 175 sacks cement.

Figures indicate bottom of formations:

Sand & Clay	170'		<u>TOPS</u>	
Shale & Shells	970'			
Shale & Sand	1490'	Heebner	3836'	(-1301)
Shale	1745'	Toronto	3858'	(-1323)
Sand	1930'	Lansing	3871'	(-1336)
Shale & Red Bed	2182'	Total Depth	4110'	(-1575)
Anhydrite	2220'			
Shale & Shells	2580'			
Lime & Shale	3865'			
Lime	4110'			
Total Depth	4110'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Walter H. Bacon  
Vice-President

Subscribed and sworn to before me this 2nd day of August, 1957.

My Commission Expires:

December 19, 1960

RECEIVED  
STATE CORPORATION COMMISSION

AUG 3 1957

CONSERVATION DIVISION  
Wichita

Luetta M. Duncan  
Notary Public

PLUGGING  
FILE SEC. 28 T. 9 R. 24W  
BOOK PAGE 32 LINE 35