


15-065-00909-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 28 Twp. 9S Rge. 24W (E) (W)  
Location as "NE/CNW&SW&" or footage from lines SW NE SE  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Kohart Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 13, 19 56  
Application for plugging filed December 18, 19 56  
Application for plugging approved December 18, 19 56  
Plugging commenced December 18, 19 56  
Plugging completed December 18, 19 56  
Reason for abandonment of well or producing formation No commercial quantities of oil found.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	12-13-56	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set No. 1 plug at 170' with 1/2 sack hulls and 15 sacks cement.  
Set No. 2 plug at 40' with 1/2 sack hulls and 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.  
Address 903 Union National Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P  
903 Union National Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of December, 1956

My commission expires April 18, 1959  
Francis E. Barham  
Francis E. Barham Notary Public.

PLUGGING  
FILE SEC 28 T 9 R 24W  
BOOK PAGE 126 LINE 22

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
 903 Union National Building  
 Wichita 2, Kansas

Kohart No. 1  
 SW NE SE Sec. 28-9S-24W  
 Graham County, Kansas

Total Depth: 4087'

Elevation: 2543' R. B.  
 Production: D & A

Commenced: 11-30-56 Completed: 12-13-56

Contractor: Imperial Oil of Kansas, Inc.  
 Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 184' with 150 sacks cement.

Figures indicate bottom of formations:

Shale & Sand	184'		<u>TOPS</u>	
Shale & Shells	340'			
Shale, Shells & Sand	2188'	Anhydrite	2188'	(-355)
Anhydrite	2240'	Heebner	3844'	(-1301)
Shale & Shells	2650'	Toronto	3866'	(-1323)
Shale & Lime	3070'	Lansing	3879'	(-1336)
Shale & Shells	3505'	Total Depth	4087'	(-1544)
Shale & Lime	3899'			
Lime	4087'			
Total Depth	4087'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: David H. [Signature]  
 Vice-President

Subscribed and sworn to before me this 18th day of December, 1956.

My Commission Expires:

April 18, 1959

Francis E. [Signature]  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 20 1956

CONSERVATION DIVISION  
 Wichita, Kansas

**PLUGGING**  
 FILE SEC 28 T 9 R 24 W  
 BOOK PAGE 126 LINE 22