

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-20361-0006

LEASE NAME Hoeting Unit

WELL NUMBER 2-2

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 29 TWP. 9 RGE. 24W (E) of (W)

COUNTY Graham

Date Well Completed 9/70

Plugging Commenced 9/4/92

Plugging Completed 9/4/92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Murfin Drilling Co., Inc.

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

PHONE# () 267-3241 OPERATORS LICENSE NO. 30606

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	258	
				4 1/2	4136	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Perf Anhydrite 2220', Dakota 1300'. RIH w/tbg to 2650'. Pumped 30 sx. 65/35 Poz, 10% gel, 50# hulls dwn tbg & spotted on btm. Pulled tbg to 1300'. Circ cmt to surface w/40 sx. 50# hulls. TOH w/tbg. Tied onto 4 1/2, pumped 25 sx. 50# hulls. MP 500#, SIP 150#. Pumped 25 sx. 50# hulls dwn 8 5/8. MP 500#, SIP 150#. JC 3:20 p.m. Witness by Carl Goodrow. 9/18 Tag cmt 484' f/s. Filled 4 1/2" csg w/redi-mix to surface.

Name of Plugging Contractor Murfin Drilling Co., Inc. License 30606

Address Wichita, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. WICHITA, KS

Patrick T. Canaday, Production Supt. (Employee of Operator), KS (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: [Signature]

(Address) Colby, KS

SUBSCRIBED AND SWORN TO before me this 13 day of October, 19 92



[Signature]
 Kerran Redington
 Notary Public

