

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
67202 TYPE OR PRINT

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-65-20533-0000  
LEASE NAME Hoeting Unit Wichita, KS

WELL NUMBER 2-6

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days  
990 Ft. from S Section Line  
1650 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 29 TWP. 9S RGE. 24W (E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Graham  
PHONE # (316 ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 3/15/72

Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 7/21/03  
Plugging Completed 7/21/03

The plugging proposal was approved on 7/21/03 (date)  
by Rich Williams w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation LKC Depth to Top 3919 Bottom 4085 TD 4160 Show depth and thickness  
of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	253	8 5/8	253	0
		Production	4155	4 1/2"	4155	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods  
used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet  
to \_\_\_ feet each set.

Plugged well as follows RIH w/ 2 3/8" tbg to 2503'. Pumped 125 sxs 60-40poz 10% gel, 400#hulls. Pulled tbg to 1428'. Pumped 55 sxs & 100#  
hulls to circ. cmt to surface. Tied onto 4 1/2" csg. Pumped 55 sxs 900# max press, 500# ISIP. Tied onto 8 5/8". Pumped 65 sxs, 100# max press,  
50#ISIP. Well P/A. Witnessed and approved by Rich Williams w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address  
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .ss.


Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on  
oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the  
same are true and correct, so help me God.

(Signature) Tom W. Nichols  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 28th day of July, 2003

Notary Public - Barbara J. Dodson Barbara J. Dodson

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED  
7-29-03  
JUL 29 2003  
KCC WICHITA

# DREILING OIL, INC.

Victoria, Kansas 67671

*24-9-87*  
API #15-065-20,533.0000

**JUL 26 1972**

Don E. Pratt Oil Operation **WELL LOG**

P/O. Drawer 370  
Hays, Kansas 67601

Company

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 20 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Sec. 29 Twp. 9 Rng. 24

Farm Geo. Nicholson No. 6

Location NE SW SE

Total Depth 4,160'

County Graham Co.

Comm. 3-8-72 Comp. 3-15-72

Elevation: 2552 K. B.

Contractor Dreiling Oil, Inc.  
Victoria, Kansas 67671

2549 D. F.

2547 G. R.

**Casing Record**

253' - 8 5/8"  
4,155' - 4 1/2"

**Cement Record**

185 sacks cement  
225 sacks common 18%  
salt and 2% CC w/5 gal.  
of B.I. flush w/10 bbl.  
salt flush

**Production:**

Figures Indicate Bottom of Formations

0'	160'	Sand & Gravel
160'	190'	Yellow Clay
190'	253'	Blue Shale
253'	1240'	Shale
1240'	1784'	Shale & Sand Streaks
1784'	1884'	Sand
1884'	2075'	Shale & Red Bed
2075'	2222'	Shale
2222'	2258'	Anhydrite
2258'	2540'	Shale
2540'	2830'	Shale
2830'	3125'	Shale & Lime
3125'	3280'	Lime & Shale
3280'	3480'	Lime & Shale
3480'	3905'	Lime & Shale
3905'	3958'	Lime
3958'	3970'	Lime
3970'	4035'	Lime & Shale
4035'	4160'	Lime
4160'	T.D.	

**LOG TOPS**

TOP 3633.5  
HEEB 3850  
TOR 2875  
LANS 3888  
BKC 4113  
LTD 4160  
RTD 4160



I, LEO F. DREILING, of the County of Graham, State of Kansas, do hereby certify that the foregoing is a true and correct copy from the Daily Log of the Don E. Pratt Oil Operation, No. 6, located in the NE 1/4 of Section 29, Township 9 North, Range 24 East, Graham County, Kansas. Witness my hand and seal of office this 16th day of March, 1972.

*Leo F. Dreiling*  
LEO F. DREILING



Subscribed and sworn to before me this 16th day of March, 1972.

*Joseph A. Hies*

**ALLIED CEMENTING CO., INC.**  
 P.O. BOX 31  
 RUSSELL, KS 67665  
 PH (785) 483-3887  
 FAX (785) 483-5566

15-065-20533-0000

\*\*\*\*\*  
 \* INVOICE \*  
 \*\*\*\*\*

Invoice Number: 090423

Invoice Date: 07/22/03

RECEIVED  
 JUL 29 2003  
 KCC WICHITA

Sold Murfin Drilling Co.  
 To: 250 N. Water St. #300  
 Wichita, KS  
 67202

R+A/RK

Cust I.D.....: Murfin  
 P.O. Number...: Hoeting #2-6  
 P.O. Date.....: 07/22/03

Due Date.: 08/21/03  
 Terms.....: Net 30

Item I.D./Desc.	Qty	Used	Unit	Price	Net	TX
Common	180.00		SKS	7.1500	1287.00	T
Pozmix	120.00		SKS	3.8000	456.00	T
Gel	26.00		SKS	10.0000	260.00	T
Hulls	5.00		SKS	18.0000	90.00	T
Holding	300.00		SKS	1.1500	345.00	T
Mileage (-55)	55.00		MILE	15.0000	825.00	T
300 sks @\$:.05 per sk per mi						
Plug	1.00		JOB	580.0000	580.00	T
Mileage pmp.trk	55.00		MILE	3.5000	192.50	T

All Prices Are Net, Payable 30 Days Following Subtotal: 4035.50  
 Date of Invoice. 1 1/2% Charged Thereafter. Tax.....: 213.88  
 If Account CURRENT take Discount of \$403.55 Payments: 0.00  
 ONLY if paid within 30 days from Invoice Date Total...: 4249.38

# ALLIED CEMENTING CO., INC. 11065

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley

DATE <u>7-21-03</u>	SEC <u>29</u>	TWP. <u>9s</u>	RANGE <u>24W</u>	CALLED OUT	ON LOCATION <u>8:20 AM</u>	JOB START <u>9:30 AM</u>	JOB FINISH <u>12:00 PM</u>
LEASE <u>Hoering</u>	WELL # <u>2-6</u>	LOCATION <u>ST Peter 3 N 3/4 E N1S</u>			COUNTY <u>Graham</u>	STATE <u>KS</u>	
<input checked="" type="checkbox"/> OLD OR NEW (Circle one)							

CONTRACTOR Ca Tools  
 TYPE OF JOB Plug Old Hole  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE 4 1/2 DEPTH \_\_\_\_\_  
 TUBING SIZE 2" DEPTH 2503'  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 900# MINIMUM 50#  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_  
 EQUIPMENT \_\_\_\_\_  
 PUMP TRUCK CEMENTER Dean  
 # 372-281 HELPER Andrew  
 BULK TRUCK \_\_\_\_\_  
 # 361 DRIVER Fuzzy  
 BULK TRUCK \_\_\_\_\_  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

OWNER Same  
 CEMENT AMOUNT ORDERED  
300 sks 60/40 100 sks 4 Hulls  
 COMMON 180 sks @ 7.15 1287.00  
 POZMIX 120 sks @ 3.80 456.00  
 GEL 26 sks @ 10.00 260.00  
 CHLORIDE \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 HANDLING 300 sks @ 1.15 345.00  
 MILEAGE 5.4/sk/mile 825.00  
 TOTAL 3269.00

REMARKS:  
Tub at 2503'. Mix 125.5k w/  
400# Hulls. Pulled to 1928'  
Circulated Cement To Surface w/  
55sk & 100# Hulls. Pulled Tub &  
Tieback to 4 1/2 csg. Pump 55sk  
Max Press 900# Shut in 500#. Pump  
65 sks down 8 3/4 Max Press 100#  
Shut in 50#  
Thank You

SERVICE  
 DEPTH OF JOB 2503'  
 PUMP TRUCK CHARGE 580.00  
 EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_  
 MILEAGE 5.5 Miles @ 3.50 192.50  
 PLUG \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 TOTAL 772.50

CHARGE TO: Murfin Drlg Co  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL \_\_\_\_\_  
 TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE John Gustina

PRINTED NAME \_\_\_\_\_

RECEIVED  
 JUL 29 2003  
 KCC WICHITA