


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 29 Twp. 9S Rge. 24W (#) (W)
Location as "NE/CNWxSWx" or footage from lines C SW NW SW
Lease Owner J. A. Terteling & Sons
Lease Name Pettett Heirs Well No. # 1
Office Address 320 Petroleum Club Bldg., Denver, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 20 19 61
Application for plugging filed December 20 19 61
Application for plugging approved 19 61
Plugging commenced December 20 19 61
Plugging completed December 20 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing K.C. Depth to top 3902 Bottom 4132 Total Depth of Well 4150 ^{6 25} Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface			202'	8 5/8		left in

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

10 sacks cement in bottom of Surface Pipe
Hole filled with Heavy Mud
5 sacks cement in top of Surface Pipe


RECEIVED
STATE CORPORATION COMMISSION
1-31-62
JAN 31 1962
CON. DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kimbark Exploration Company
Address 201 University Blvd., Denver, Colorado

STATE OF Colorado COUNTY OF Denver, ss.
C. H. Shankland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.
(Signature) C. H. Shankland
320 Petroleum Club Bldg Denver Colo
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of January, 1962
My commission expires November 18, 1963
Edwin F. Fick
Notary Public.



PETTETT #1 WELL

Location: SW NW SW Section 29
T-9-S, R-24-W
Graham County, Kansas

Spudded: 12/11/61
Completed: 12/19/61

Owner: J. A. Terteling and Sons
Petroleum Club Building
Denver 2, Colorado

Contractor: Kimbark Exploration Co.
201 University Blvd.
Denver 6, Colorado

Surface Casing: 8 5/8" ss casing cemented at 202' K.B. with 160 sacks quick set.

Oil String: None

LOG

Figures indicate bottom of formation

206	Shale
335	Shale
1,190	Shale
1,620	Shale & Sand
1,870	Sand & Shale
2,232	Shale
2,415	Anhydrite-Shale
2,620	Shale
2,725	Shale & Shells
2,890	Lime
3,020	Lime
3,070	Lime
3,250	Lime & Shale
3,310	Shale & Lime
3,390	Lime
3,473	Lime
3,555	Lime
3,618	Lime
3,685	Lime
3,780	Lime
3,860	Lime
3,933	Lime
3,950	Lime
4,005	Lime-Shirt
4,075	Lime
4,106	Lime
4,160	Rotary Total Depth

RECEIVED
STATE CORPORATE COMMISSION
JAN 31 1962
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, W. K. Arbuckle, President of Kimbark Exploration, hereby certifies that the above is a true and correct log of the formations encountered in drilling the Pettett #1 as shown in the daily drilling reports.

KIMBARK EXPLORATION COMPANY

W. K. Arbuckle
W. K. Arbuckle, President

STATE OF COLORADO) ss
CITY & COUNTY OF DENVER)

Be it remembered that on this 22nd day of January A.D. 1962, before me, Marilyn A. Rehm, a Notary Public, personally appeared W. K. Arbuckle, President of Kimbark Exploration Company, a Colorado Corporation, who is personally known to me and known to me to be the President of said Corporation, and the same person who executed the foregoing instrument, and he duly acknowledged the execution of the same for and on behalf of and as the act and deed of said Corporation.

WITNESS my hand and official seal:
My Commission Expires November 15, 1964

Marilyn A. Rehm
Notary Public