


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 29 Twp. 9S Rge. 24W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner C-G Drilling Co. & J. A. Terteling & Sons
Lease Name Nickelson Well No. #1
Office Address 107 Rule Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed November 30 19 63
Application for plugging filed November 30 19 63
Application for plugging approved November 30 19 63
Plugging commenced November 30 19 63
Plugging completed November 30 19 63
Reason for abandonment of well or producing formation Too low structurally

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4155 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	223'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy mud to 540'.
Set Plug. Put in 20 sks. cement.
Filled with heavy mud to 210'. Set
plug. Put in 20 sks. cement. Filled
with heavy mud up to 40'. Filled to
top with 10 sks. cement + 1 sk. hulls.

RECEIVED
STATE CORPORATION COMMISSION
12-6-63
DEC 6 1963

CONSERVATION DIVISION
Wichita, Kansas


Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
G. F. Galloway

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Bldg.
(Address)

My commission expires _____
Subscribed and sworn to before me this 4th day of December, 19 63
May 20, 1967
Vicky Jacobs
Notary Public.



W E L L L O G

OPERATOR	C-G Drilling Co.	SEC.	29-9S-24W
WELL NAME	Nickelson #1	LOC.	NW NW SE
TOTAL DEPTH	4155'	COUNTY	Graham
COMM.	11/21/63 COMP. ^{11-30-63 RT} 12/1/63 KCC	STATE	Kansas
RIG NO.	#2	ELEVATION	2557 R.B.
CASING:	Set 223' (7 jts.) 8-5/8" OD Surface Casing.	PRODUCTION:	D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	193	Sand		
193	1507	Shale	1000' - 0°	
1507	1537	Sand		
1537	1780	Shale		
1780	1975	Sand		
1975	2225	Red Bed	2000' - 0°	
2225	2270	Anhydrite		
2270	2685	Shale-Shells		
2685	3805	Shale-Lime	3000' - 0°	
3805	4155	Lime		DST #1 4022-50 DST #2 4050-87

RECEIVED
STATE CORPORATION COMMISSION

DEC 6 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
G. F. Galloway
day of December, 1963.

Vicky Jacobs
Vicky Jacobs - Notary Public



SUBSCRIBED AND SWORN TO, BEFORE ME, THIS

My commission expires:
May 20, 1967