

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

Received
KCC
11-25-1974

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gib Scheck of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Scheck guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Nickelson 'A' Well No. 1

Location: SE-SE-SW Sec. 23 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4060 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Scheck was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.
4060'--4 1/2" Production casing cemented on bottom with 125 Sx. Top of perforations @ 3848'. Top of cement @ 3500'.

Push plug to 3600', sand back to 3550' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Dinkel
Conservation Division Agent