

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-065-21,582
5:45 PM - 3-21-82

Dear Sir:

Mr. Dean Beckner of Reach Oil Corp. has this date requested permission to plug the following described well:
3751 E. Douglas - Wichita - 67218

Operator's Full Name: Reach Petroleum Corp.

Complete Address: 3751 E. Douglas - Wichita, Kansas 67218

Lease Name: Mickelson Well No. 1

Location: N2-NE-NE Sec. 23 Twp. 9 Rge. 24 (E) (W)

County: Graham Total Depth: 4210'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Dean Beckner was instructed to plug the well as follows:

8 5/8" @ 259' w/200 sx 69/40 pozmix 22 gel-32 cc (Halliburton)
Ordered 135 sx 50/50 pozmix 49 gel-39 cc + 8 5/8" plug
Spotted 70 sx @ 1230' - 40 sx @ 250' - 10 sx @ 40'-0'
on solid bridge - 10 sx in Rat hole - 5 sx in mouse hole.
Use heavy mud between all plugs

(cont by Halliburton)

Very truly yours,

Dennis L. Daniel
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
3-17-82
MAR 17 1982
CONSERVATION DIVISION
Wichita, Kansas