



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
1-6-71
JAN 6 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply, Inc., has this date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Woodman-Iannitti Oil Company,

Complete Address: 706 Union National Building, Wichita, Kansas.

Lease Name: Nickelson Well No. A-2

Location: CW/2-W/2-SE Sec. 24 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4020' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

185'--8 5/8" Surface casing, cement circulated with 140 Sx.
4017'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to 4001'. Top perforations @ 3888'.

Push plug to 3825' sand to 3800' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Sx. cement, staged.

Very truly yours,

Conservation Division Agent