



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. J. Iannitti of Woodman-Iannitti Oil Co., has this date requested permission to plug the following described well:

Mr. Iannitti guarantees payment of the plugging fee.

Operator's full Name: Woodman-Iannitti Oil Company,

Complete Address: 706 Union National Building, Wichita, Kansas.

Lease Name: Nickelson Well No. A-1

Location: NW-NW-SE Sec. 24 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4020' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Iannitti was instructed to plug the well as follows:

185'--8 5/8" Surface casing, cement circulated with 140 Sx.  
4020'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to 4004'. Top perforations from 3833' to 3837'.

Squeeze 5 1/2" casing with 1 sack hulls, 31 sacks gel and 105 Sx. cement, staged. Squeeze annulus with 4 sacks hulls then 7 sacks gel and finally 35 Sx. cement.

Very truly yours,

W. L. Nichols  
Conservation Division Agent