

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Michael of Sage Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Monarch Oil & Gas Company.

Complete Address: 1005 Wichita Plaza, Wichita, Kansas.

Lease Name: Pettett Well No. 1

Location: SE-SE-SE Sec. 25 Twp. 9 Rge. (E)(W)24

County Graham Total Depth 4090 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Michael was instructed to plug the well as follows:

207' --8 5/8" Surface pipe, cement circulated with 150 Sx. Dakota section from 1675' to 1885'.

Circulate hole with heavy mud and displace 100 Sx. cement thru DP. from 2005' to 1575. Pull DP. to 210' and displace 20 Sx. cement thru DP. DP. set plug @ 40' and 10 Sx cement to bottom of cellar.

STATE CORPORATION COMMISSION

7-21-67  
JUL 21 1967

Very truly yours,

*M. L. Nichols*

CONSERVATION DIVISION  
Wichita, Kansas  
Conservation Division Agent