

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
5-20-74
MAY 20 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Keener of PMI has this
date requested permission to plug the following described well:

Mr. Keener guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: P. O. Box #922, Great Bend, Kansas.

Lease Name: Moore Well No. 2

Location: SE-SW-SW Sec. 27 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4110' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Keener was instructed to plug the well as follows:

246'--8 5/8" Surface casing, cement circulated.

4109'--4 1/2" casing cemented on bottom with 250 Sx. Top perforations from 3906' to 3910'.

Sand well back to 3850' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent